

ERCDC
GB. 30
D598
c. 2

CALIFORNIA ENERGY COMMISSION
LIBRARY COPY

**DIRECT USE OF
GEOTHERMAL ENERGY
AT THE SAN BERNADINO
WASTEWATER
TREATMENT PLANT**

NOVEMBER 1983

**CALIFORNIA
ENERGY
COMMISSION**

P500-83-020

C
O
N
S
U
L
T
A
N
T
R
E
P
O
R
T

ERDC
G.B.30
D598
C.2

ANGY

California Energy Commission

DIRECT USE OF GEOTHERMAL ENERGY
AT THE SAN BERNARDINO
WASTEWATER TREATMENT PLANT

Contract Number 500-81-005

San Bernardino Municipal Water Department
San Bernardino, California

November 1983

CALIFORNIA ENERGY COMMISSION

FEB 28 1984

LIBRARY

ABSTRACT

This report provides a chronological and technical evaluation of the successful use of geothermal energy in San Bernardino, California, to provide heating for wastewater treatment facilities.

The annual energy cost saving for the currently tested system is more than \$29,425 for the single anaerobic digester now being heated. Expansion of the wastewater facility, resulting in two additional digesters, could result in three geothermal heated digesters on line--a minimum of two. This expanded usage, together with expected natural gas price increase, should result in recovery of all investment costs in less than 10 years.

TABLE OF CONTENTS

	<u>page</u>
LIST OF FIGURES	iv
LIST OF TABLES	v
1. INTRODUCTION	1
2. RESOURCE CONFIRMATION AND DEVELOPMENT	2
2.1 Recommendation for a Drilling Program	2
2.2 Permits and Agreements	6
2.3 Selection of Drilling Contractor	7
2.4 Drilling, Logging, Completion of Thermal Gradient Wells	7
2.4.1 Stratigraphic Summary	8
2.4.2 Geologic Structure and Distribution of Thermal Waters	8
2.4.3 Hydrology of Thermal Waters	12
2.4.4 Recommendations for Production Well	13
3. ACQUISITION OF PRODUCTION WELL AND INSTALLATION OF TRANSMISSION LINES	14
3.1 Acquisition of Production Well	14
3.2 Rework of Meeks and Daley #66	16
3.3 Transmission Pipeline Installation	20
4. SYSTEM DESIGN, TESTING, START-UP	24
4.1 System Design	24
4.1.1 Heat Exchanger	24
4.1.2 Pump and Motor-Meeks and Daley #66	28
4.1.3 Disposal of Geothermal Fluid	31
5. PROJECT COST SUMMARY AND CONCLUSIONS	32
5.1 Projected Natural Gas Savings	32
5.2 Cost Comparison of Geothermal Energy to Natural Gas	32
5.3 Conclusion	35

TABLE OF CONTENTS (cont.)

APPENDICES

A. Stratigraphic and Geologic Data - Temperature Gradient

Plate II

Plate III

Plate IV

Plate V

Plate VI

Plate VII

B. Data Concerning TG No. 1

C. Data Concerning TG No. 2

D. Data Concerning TG No. 4A

E. Data Concerning TG No. 5A

F. Temperature Profiles

Meeks & Daley #66

TG No. 2

LIST OF FIGURES

	<u>PAGE</u>
1. Location Map San Bernardino Vicinity.....	3
2. Proposed Casing Program for 1500' Temperature Gradient/Observation Well.....	5
3. Structure Contour Map on Top of the San Timoteo Formation.....	9
4. Maximum Temperature Contour Map.....	11
5. Proposed Geothermal Production Well Properties and Existing Meeks and Daley Well No. 66.....	15
6. Meeks and Daley Well No. 66 Temperature Gradient Log.....	21
7. Pipeline Route From Meeks and Daley Well No. 66 to Digester Area of Wastewater Treat- ment Plant.....	23
8. Piping and Instrumentation Diagram Geothermal Heating of One Anaerobic Digester.....	25

LIST OF TABLES

	<u>PAGE</u>
1. Driller's Log From Meeks and Daley Well No. 66	17
2. Thermal Survey Data From Meeks and Daley Well No. 66.....	18
3. Temperature and Flow Test - Meeks and Daley Well No. 66	19
4. Design Criteria For Determining Pipe Diameter.....	20
5. Key to Drawing Symbols.....	26
6. Analysis of Water Samples From Meeks and Daley Well No. 66	27
7. Flow Test on East Digester Heat Exchanger Meeks and Daley Well No. 66 Flowing Artesian.....	29
8. Flow Test on East Digester Heat Exchanger Meeks and Daley Well No. 66 Pumped	30
9. Summary of Project Costs for Direct Use of Geothermal Energy at the San Bernardino Wastewater Treatment Plant	33

1 - INTRODUCTION

In June, 1981, the San Bernardino Municipal Water Department completed a study funded by the Department of Energy entitled, "Feasibility Study For Wastewater Treatment Utilizing Geothermal Energy In San Bernardino". The study indicated that use of low temperature geothermal heat for heating primary anaerobic digesters was feasible.

Following completion of the feasibility study, an agreement was executed between the California Energy Commission and the Board of Water Commissioners, City of San Bernardino, to implement the project. The State agreed to fund 90% of the project costs up to a maximum of \$390,600. The project was segmented into the following components: (1) resource confirmation and development, including the drilling and logging of temperature gradient wells and the development/acquisition of a production well; (2) purchase and installation of transmission and distribution facilities; (3) retrofit of heat exchangers at the anaerobic digesters; and (4) system testing and implementation of direct use of geothermal heat for the digesters.

The project is complete and heating one primary anaerobic digester. There is capability and capacity in the production well and transmission facilities to heat two additional digesters. Annual offset of natural gas/methane to fuel a boiler to heat one digester by utilizing geothermal energy is 43,800 therms. When all three digesters are heated with geothermal energy, the total offset of natural gas/methane annual is 164,250 therms. The annual cost savings by utilizing geothermal energy to heat one digester at the current natural gas cost is \$29,425.

2 - RESOURCE CONFIRMATION AND DEVELOPMENT


2.1 Recommendation for a Drilling Program.

The first phase of this project was to conduct additional studies and field investigations to further evaluate the geothermal resource of the area.

The California Division of Mines and Geology conducted a geothermal assessment study in the San Bernardino area to investigate the low temperature geothermal resource. The report issued as a result of their study entitled, "Resource Investigation of Low and Moderate Temperature Geothermal Areas in San Bernardino, California", identified three active designated geothermal areas as the most likely sites for geothermal exploration and development. The South San Bernardino area identified in the report was chosen as the area for further investigation since it was close to the direct use application. The report further states that the next phase of assessing or developing the geothermal resources of San Bernardino should be an exploratory drilling program, or a deep monitoring well drilling program.

Republic Geothermal, Inc. was selected to develop a plan for drilling thermal gradient/observation wells and a production well. The report was submitted in November, 1981 and then amended subsequent to a meeting with representatives of the California Division of Mines and Geology and California Energy Commission in December, 1981. The project area (Figure 1), identified as the South San Bernardino Geothermal area, is one in which there are several wells that produce waters whose temperatures range from 24°C to 56°C. Most of these wells are located near the suspected trace of the Loma Linda fault; however, their precise relationship to the fault was not known. Meeks and Daley #66 Well is located within the project area. The well is a known hot water well with temperature recordings of 56°C. It was decided to conduct the drilling of thermal gradient wells rather than drilling a production well immediately near the Meeks and Daley #66 Well. A possibility existed of finding a resource hotter than that supplying Meeks and Daley #66 Well by exploring along the fault. The temperature gradient wells also provided lithologic and temperature

FIGURE 1



1/10 1971

FIGURE 1

LOCATION MAP
SAN BERNARDINO VICINITY

information needed to define the geothermal reservoir, and to design and locate future geothermal production wells.


The thermal gradient wells consist of a 2-7/8 inch diameter steel tube capped on the bottom, encased in cement, filled with water, and left undisturbed until the temperature of the water in the tube approaches equilibrium with temperature in adjacent sediments (Figure 2). The temperatures are measured to obtain the rate of increase of temperature with increasing depth, and to define a temperature profile which indicates zones of conductive and/or convective heat flow. The designed casing size will permit perforating tools into the well for later conversion into observation wells used for monitoring reservoir behavior. As part of the drilling program, self-potential, resistivity, gamma ray, and temperature logs for each thermal gradient well were conducted prior to cementing in the casing. This information, combined with drillers' logs, drill cutting analysis, and hydrologic data, provides for optimum design of production wells, and a greater understanding of the location of the geothermal resource.

Sites for the thermal gradient wells were recommended with the following logistical considerations in mind:

1. Distance from the wells to the wastewater treatment plant should be minimized while remaining consistent with the geological constraints.
2. Thermal gradient wells should be drilled predominantly on the west side of the San Bernardino County Flood Control District's canal to minimize the cost of crossing the canal with pipelines from a production well.
3. Thermal gradient well sites should be located on lands on which the San Bernardino Municipal Water Department has or can acquire the right to drill.

FIGURE 2

PROPOSED CASING PROGRAM FOR 1500' TEMPERATURE GRADIENT/OBSERVATION WELL



The location of the production well to be drilled was to be determined after review of thermal gradient drilling results, geology, flow rates, and land ownership information. The two most important factors in selecting the site are resource temperature and the attainable flow rate. The other variables to consider are the distance between the production well and the wastewater treatment plant, and the degree of difficulty involved in placement of transmission pipeline facilities.

2.2 Permits and Agreements.

In order to conduct the drilling program and place thermal gradient wells on the non-department owned land, agreements were negotiated with two local agencies. A permit was obtained from the San Bernardino County Flood Control District granting permission to construct up to two thermal gradient wells on the west levee of Twin Creek Channel. A second agreement was entered into with the National Orange Show to conduct exploratory drilling for up to three thermal gradient wells. Agreement could not be reached for the placement of a production well upon National Orange Show property; however, permission granted from the two agencies provided sufficient land area for optimum placement of thermal gradient/observation wells along or near the Loma Linda Fault.

Notices of Intent to Drill a Geothermal Resource Well were submitted to the State of California, Division of Oil and Geology for four thermal gradient well sites in December, 1981. Included with the notices was a copy of the intended drilling program for review and approval.

A Notice of Exemption was issued in December, 1981 for the drilling of up to five thermal gradient wells by the Division of Oil and Gas, fulfilling the CEQA requirements for the first phase of the drilling program.

Reports on Proposed Geothermal Operations for the four thermal gradient wells were issued by the Division of Oil and Gas in February, 1982.

2.3 Selection of Drilling Contractor.

Plans and specifications were developed by November, 1981 for the drilling and development of up to five thermal gradient wells on a lump-sum basis. Authorization was granted from the Board of Water Commissioners to advertise and receive bids for the drilling of the thermal gradient wells. Bids received were opened on December 30, 1981. A review of the bids received was conducted by Water Department staff and representatives from Republic Geothermal, Inc. It was the general consensus that the lump sum bids should be rejected, and the specifications modified to receive bids on a time and material basis, thereby putting more risk on the Water Department to reduce the contractual costs of drilling. The four drilling contractors who bid on the project related that they were reluctant to competitively bid due to four conditions: (1) shallow groundwater; (2) areas of large boulders that appear on other well logs within the drilling area; (3) artesian pressure; and (4) unknown water temperature.

As a result of the information obtained, the bids for drilling up to five thermal gradient wells were rejected by the Board of Water Commissioners, and authorization was granted to modify the specifications and advertise and receive bids on a time and material basis. Bids were received for the drilling program again and on February 2, 1982, the contract was awarded to McCalla Bros., Inc. Republic Geothermal, Inc. was retained to provide field supervision, and to conduct all logging and testing requirements for the thermal gradient wells.

2.4 Drilling, Logging, Completion of Thermal Gradient Wells.

The thermal gradient drilling program began March 16, 1982 and concluded on May 11, 1982. During that period, four thermal gradient wells were drilled, logged, and cased. The four wells (TG-2, TG-1, TG-5A, and TG-4A) were drilled to depths ranging from 815 to 1500 feet. Drill cuttings were sampled at nominal ten foot intervals. In addition, open hole intervals were logged for self-potential and resistance in TG-2, TG-1, and TG-5A using a Mt. Sopris Model 1000-C portable logging unit and, in TG-4A, with a Gearhart-Owens unit by

Southwest Drilling Company. Under conditions in which the 1000-C tool could not be used, holes were gamma ray logged through the 2-7/8 inch tubing and cement.

To obtain accurate temperature measurements and to isolate thermal aquifers later in the project, 2-7/8 inch capped tubing was installed in each hole and pressure grouted from bottom to top by Halliburton Services.

2.4.1 Stratigraphic Summary.


The stratigraphy of the project area, to the depths drilled in the four temperature gradient/observation wells, comprises two units: The Tertiary Age San Timoteo Formation and the overlying Quaternary Age Santa Ana River alluvium. Both are composed of intercalated beds of unconsolidated coarse angular sands, gravels, clays, and all gradations between the three. No alteration, cementation, or grain coatings were noted. Discrete beds are usually two to ten feet thick; however, some sands are up to 45 feet thick. Both the alluvium and the San Timoteo sediments were deposited in stream channels and on adjacent river banks (alluvial plains).

The salient features of each hole are submitted and attached as Appendixes B-D. Plates II - V, shown in Appendix A, depict the detailed stratigraphy and serve to document the impossibility of correlating beds between the thermal gradient wells. Figure 3 is a structure contour map drawn on top of the San Timoteo Formation. The map is based on the depth to the top of the San Timoteo Formation in each of four gradient holes drilled, indicating that the San Timoteo Formation dips about 7 degrees to the west in this area.

2.4.2 Geologic Structure and Distribution of Thermal Waters.

The relative unconsolidated nature of the rocks penetrated by the four wells, together with their origin within braided stream channels whose courses often shift in time and in space, create a situation wherein it is almost impossible to accurately determine the attitude of the sediments. The incom-

FIGURE 3
STRUCTURE CONTOUR MAP
ON TOP OF THE SAN TIMOTEO Fm



petence of these units precludes the direct detection of faults that transect the area. Plates VI and VII, as shown in Appendix A, are geologic cross sections that depict interpreted stratigraphic, structural, and thermal conditions in the project area.


It appears likely that the locations of the old Warm Creek Channel and of its main northeasterly trending tributary may be fault-controlled and that these faults intersect the northwest-trending Loma Linda fault in the vicinity of the Meeks & Daley #66 well. This fault intersection probably provides a "high" permeability path that allows the warm thermal fluids to rise to shallow depths or even to the surface, as suggested by the name Warm Creek. This theory is supported by the temperature distribution of fluids encountered in existing water wells that, southeastward along most of the Loma Linda fault in this area, become much cooler than those flowing from the Meeks & Daley #66. The exception to this trend is in an area to the southeast of the Wastewater Treatment Plant, on the golf course, where the well water temperatures are also high (well #81, 51°C). This fact suggests the presence of a second fault orthogonally intersecting the Loma Linda fault and creating conduits for upward percolation of hotter waters.

Simultaneous analyses of the temperature profiles and the lithologies recorded in the gradient holes (Plates II-V) show that there are several discrete aquifers having different temperatures at varying depths within both the alluvium and the San Timoteo Formation. Figure 4 is a map of the maximum temperatures measured in the four gradient holes and in the Meeks & Daley #66, contoured without regard to depth. The contour pattern confirms that temperatures decrease to the southeast and east away from the Meeks & Daley #66 and TG-2 area.

These data reinforce the theory that the thermal fluids are rising in the area of the Loma Linda and Warm Creek fault intersection and then flowing into a number of separate cold water aquifers in varying amounts. The variable mixing rates, permeabilities of the aquifers, and rates of water movement within each aquifer account for the variable temperature distribution east and southeast of the source area near Meeks & Daley #66.

FIGURE 4

MAXIMUM TEMPERATURE CONTOUR MAP



The Loma Linda fault apparently acts as an aquiclude along its strike and may deflect the thermal waters toward the east and southeast. This is supported by available water well data that show that there is no apparent thermal plume spilling across the fault to the west.

2.4.3 Hydrology of Thermal Waters.

Analyses of both the stratigraphic and temperature data lead to a conclusion that the distribution of thermal waters in the project area is controlled primarily by the location of the Loma Linda fault and by its intersection(s) with at least one (and probably two) northeast-striking fault(s). Of secondary importance is, of course, the distribution of permeable horizons adjacent to and transected by the Loma Linda fault.

As has been previously noted, TG-2 appears to be located near a thermal water upwelling site that may exist at the junction of the Loma Linda and Warm Creek faults. Warm (56°C) waters tapped in the Meeks and Daley #66 and in TG-2 tend to flow southeastward along the semipermeable to impermeable boundary created by the Loma Linda fault. They were encountered at varying depths in TG-5, TG-4A, and TG-1, and at varying temperatures, all of which were cooler than 56°C .

It appears then that the waters tapped in the latter three wells were mixed to varying degrees with nonthermal waters that saturate both the alluvium and the San Timoteo sediments in areas away from the Loma Linda fault.

The hydrothermal system in the project area is more complicated than was initially suspected so that with the limited factual information available, conclusions can be drawn only on broad hydrologic principals. Nevertheless, the system described above is consistent with the data recorded and sound decisions can be made concerning the best site for the production well.

2.4.4 Recommendations for Production Well.

Based upon the results obtained from the thermal gradient well drilling program, the recommended site for drilling a production well was \pm 250 feet northwest of Meeks and Daley #66. This location was selected to be the most cost effective with regard to resource temperature and logistics of the transmission pipe from the well site to the Wastewater Treatment Plant. The pilot hole was to be drilled to a depth of 1,000 feet, logged, and then a determination made as to the depth of the production well and the production interval. The anticipated temperature of the resources was 56°C (133°F) or slightly higher.

An alternate site \pm 20 feet north of TG-2 was selected if access could not be gained to the primary site. The anticipated resource temperature at the alternate site was 56°C or higher.

3 - ACQUISITION OF PRODUCTION WELL AND INSTALLATION OF TRANSMISSION LINES


With the drilling program complete and the optimum location of a production well known, the next objective was to acquire the right to drill a production well on the proposed well site. The property is owned by the National Orange Show. Previous agreement had been reached with the Board of Directors for the National Orange Show for the drilling of up to three thermal gradient/observation wells. Numerous delays were encountered in trying to reach an agreement with the National Orange Show for use of their property. With the delays encountered, an alternate site for placement of a production well was selected. The site, located \pm 250 feet west of Meeks and Daley #66 on property adjacent to Warm Creek Channel, is owned by the San Bernardino County Flood Control District. A permit was granted by the District for the construction of a well and appurtenant facilities in September, 1982 for a twenty year period. By obtaining the use of this site, the only obstacle that remained was obtaining a pipeline easement from the well site to Arrowhead Avenue on property owned by the National Orange Show.

3.1 Acquisition of Production Well.

Contact with Meeks and Daley Water Company had been made at the start of the project to determine if there was a possibility of acquiring Meeks and Daley #66. At the time, they were not interested in selling Meeks and Daley #66. It was also anticipated that the drilling program would locate a resource with a higher temperature.

With the results of the resource confirmation program and delays in obtaining rights to drill a production well on National Orange Show property, contact was made again with Meeks and Daley Water Company for the acquisition of Meeks and Daley #66 well. Negotiations began in August, 1982 and agreement was reached in November, 1982 for the acquisition of Meeks and Daley #66 and an area around the well to connect it to the site obtained from the San Bernardino County Flood Control District. The total acquisition cost for the well and plot of land was \$40,000 (Figure 5).

FIGURE 5



SAN BERNARDINO MUNICIPAL WATER DEPARTMENT			
PROPOSED GEOTHERMAL PRODUCTION WELL PROPERTIES & EXISTING MEKS & DAILY WELL			
DRAWN BY <i>M. Ross</i>	CHECKED BY	SCALE 1" = 100'	C.O. NO.
APPROVED BY	DATE 11-9-83		REF.
SHEET		OF	

Meeks and Daley #66 was drilled by cable tool in 1966 to a total depth of 975 feet according to the drilling log (Table 1). The proposed use of the well was for domestic and irrigation water. The well was backfilled from 700 feet to 975 feet apparently in an effort to seal off strata containing elevated boron. The well was cased throughout the depth of the hole with 20-inch diameter 6 gauge casing perforated at all hot and cold water bearing strata, using a Mills Mechanical Knife with a 2½ inch by 3/8 inch blade.

In approximately 1977, the well began to flow artesian at a rate of 1,350 gpm, with a water temperature of 135°F to 140°F. Geothermal Surveys, Inc. attempted a thermal log in May, 1980. The results are displayed in Table 2. The well could only be logged to a depth of 160 feet due to the artesian flow and the large diameter pump equipment set inside the casing.

3.2 Rework of Meeks and Daley #66.

Upon entering escrow for the purchase of Meeks and Daley #66, authorization was granted by Meeks and Daley Water Company for the Water Department to remove the existing pumping equipment, bail the well, and set equipment to conduct carbon dioxide vapor pressure testing.

The last week of December, 1982, the existing equipment was pulled from the well and the well was then bailed to a total depth of 945 feet from 857 feet. The carbon dioxide release test was then conducted on the well by setting a 35 gpm, 100 psi submersible pump 60 feet into the well which was flowing in excess of 1,000 gpm. The preliminary findings indicate a carbon dioxide vapor pressure of 8 to 9 psi.

In January, 1983, flow tests were conducted on the well. In order to conduct the flow and temperature tests, a valved 12-inch diameter pipe was inserted in the 20-inch diameter well casing and a well seal kit was inflated to control the artesian flows. Results of the first flow and temperature tests are displayed on Table 3. The temperature remained at 55°C at flows varying from 500 gpm up to 2,500 gpm.

MECKS AND DALEY WATER COMPANY

60.0 feet West of Arrowhead Avenue - 90.0 feet North of Central Avenue

Diameter - 20 Inches, 6 Gage Casing - Double
 Depth - 975 Feet
 Drilled - May, 1966
 Drilled by - R. & W. Drilling, Inc.

0	Ft.	to	60 Ft.	sand and gravel
60	Ft.	to	64 Ft.	clay
64	Ft.	to	210 Ft.	blue silt and sand
210	Ft.	to	220 Ft.	gravel and rock - up to 4 inches
220	Ft.	to	244 Ft.	blue clay and gravel
244	Ft.	to	255 Ft.	gravel and rock - up to 4 inches
255	Ft.	to	262 Ft.	brown clay and gravel
262	Ft.	to	280 Ft.	brown clay
280	Ft.	to	290 Ft.	small gravel
290	Ft.	to	310 Ft.	brown clay and gravel
310	Ft.	to	315 Ft.	sand and gravel
315	Ft.	to	351 Ft.	brown clay and gravel
351	Ft.	to	379 Ft.	blue clay and sand with streaks
379	Ft.	to	385 Ft.	blue clay
385	Ft.	to	387 Ft.	brown sand, fine
387	Ft.	to	398 Ft.	blue fine sand, tight
398	Ft.	to	415 Ft.	blue clay with gravel streaks
415	Ft.	to	450 Ft.	blue sandy clay
450	Ft.	to	461 Ft.	cemented sand and gravel
461	Ft.	to	467 Ft.	blue sandy clay
467	Ft.	to	503 Ft.	blue sandy clay with gravel
503	Ft.	to	570 Ft.	brown sand and gravel
570	Ft.	to	575 Ft.	brown sand and gravel - up to 4 inches
575	Ft.	to	612 Ft.	brown sandy clay
612	Ft.	to	617 Ft.	black sticky clay
617	Ft.	to	635 Ft.	brown clay
635	Ft.	to	695 Ft.	gray sand and gravel - up to 4 inches
695	Ft.	to	703 Ft.	tight sand, small gravel, brown clay
703	Ft.	to	745 Ft.	tight sand and small gravel
745	Ft.	to	791 Ft.	silt, fine sand with blue clay
791	Ft.	to	801 Ft.	cemented sand and pea gravel
801	Ft.	to	809 Ft.	tight sand and small gravel
809	Ft.	to	867 Ft.	sand and gravel - up to 4 inches
867	Ft.	to	885 Ft.	sand and gravel - tight, clean
885	Ft.	to	930 Ft.	sand, pea gravel - tight with clay
930	Ft.	to	939 Ft.	sand and gravel, small
939	Ft.	to	955 Ft.	sand and gravel and rocks
955	Ft.	to	967 Ft.	sand, silt with streaks of clay
967	Ft.	to	975 Ft.	brown and blue clay

Driller's Log from Meeks and Daley Well
 No. 66

TABLE 2

Thermal Survey Data from Meeks and
Daley Well No. 66*

Flow: (Artesian)	875 gpm
Temperature at outflow:	55°C 131°F
Field pH	7.0
Temperature at depth:	20 ft. - 63.1°C 145.6°F
	160 ft. - 63.0°C 145.4°F
Thermal Gradient:	20 - 160 ft - .07°C/100 ft. .13°F/100 ft.
*From analysis performed by Geothermal Surveys, Inc. in May 1980.	

TABLE 3

TEMPERATURE AND FLOW TEST
MEEKS & DALEY #66

January 8, 1983

Flow Rate (GPM)		MINUTES AT FLOW RATES					
		<u>5</u>	<u>10</u>	<u>15</u>	<u>20</u>	<u>25</u>	<u>30</u>
500	Temperature (°F)	127.00	128.00	128.00	128.00	129.00	131.00
	Pressure (psi)	12.00	11.75	11.75	11.75	11.75	11.75
	pH	8.25	8.25	8.30	8.22	8.25	8.30
1,000	Temperature (°F)	130.60	129.90	129.80	129.90	130.00	130.00
	Pressure (psi)	10.50	10.00	10.00	10.00	10.00	10.00
	pH	8.25	8.25	8.25	8.35	8.62	8.62
1,500	Temperature (°F)	130.70	131.00	131.00	131.00	131.00	131.00
	Pressure (psi)	9.00	8.50	8.50	8.50	8.50	8.50
	pH	8.30		8.62			8.62
2,000	Temperature (°F)	131.20	131.10	131.00	131.00	131.00	131.00
	Pressure (psi)	7.00	6.75	6.75	6.75	6.75	6.75
	pH	8.82		8.82			8.82
2,500	Temperature (°F)	131.00	131.00	131.00	130.90	130.90	130.90
	Pressure (psi)	4.50	4.50	4.50	4.50	4.50	4.50
	pH	8.88	8.88	8.86	8.86	8.80	8.86

Static Start: Pressure: 12.5 psi
 Start Temperature: 110.0 °F
 Time to sand surge: 2.5 Hours
 Well Seal Bag Pressure: 24.0 psi
 Start Time: 10.30 a.m.
 Finish Time: 2:45 p.m.

Temperature profiles for Meeks and Daley #66 are displayed on Figure 6. Because the well was flowing, the temperature curve is relatively flat. The highest temperature recorded was 59°C at a depth of 825 feet. More recent temperature profiles were conducted and are displayed in Appendix F.

Subsequent to the initial tests performed, the well head was reequipped to allow for total shut off of the well. A blind flange was installed on top of the casing and three gate valves on the 20-inch casing to allow for controlled flows to the treatment plant, discharge to the Flood Control Channel, and a valve for an additional transmission line connection.

3.3 Transmission Pipeline Installation.

In June, 1983, contact was made with various suppliers of insulated pipe to obtain a better working knowledge of the various products and estimated costs. After review of the products and literature, formal specifications were developed for furnishing 4400 feet of 8-inch insulated pipe.

The design criteria for determining pipe size are displayed on Table 4.

TABLE 4
DESIGN CRITERIA FOR DETERMINING PIPE DIAMETER

Number of digesters to be heated: 2 - 2 million gallon capacity.

Maximum day heat requirement per digester: 1.5×10^6 Btu's.

Flow requirement based on an exchange Δt of 16°F: 500 gpm.

Distance from well to digester: 4200 feet.

Coefficient of roughness for epoxy-lined pipe: 130(c).

Maximum acceptable head loss in 4200 feet of pipeline: 25 feet.

Maximum allowable heat loss @ 500 gpm: 1°F in 4200 Feet.

FIGURE 6

SAN BERNARDINO MUNICIPAL WATER DEPARTMENT

MECKS & DALEY WELL # 66
TEMPERATURE GRADIENT LOG

C.D. NO.

SCALE


CHECKED BY

DRAWN BY

REF.

SHEET OF

DATE



A contract was awarded in February, 1983 to Thermal Pipe System, Inc. for 4400 feet of 8-inch inside diameter epoxy-lined preinsulated and cased pressure pipe manufactured by Johns-Mansville Corporation. The core pipe is Class 150 Asbestos Cement pressure pipe with a Class 1500 Asbestos Cement sewer pipe casing. The pipe has ring-tite joints allowing for fast and simple installation.

Within two weeks of contract award, the pipe was delivered by the supplier. To facilitate the installation, the Water Department scheduled two crews for the project. One crew started at the heat exchangers located at the Wastewater Treatment Plant, and the other crew started at the well site. Installation of the pipeline within the Treatment Plant property took longer than planned due to a high groundwater table and the large number of underground pipes within the transmission pipeline route. Thirty-two underground utility lines were encountered, and the groundwater table was within three feet of the surface. Air release valves were installed along the pipeline to prevent air locking caused by carbon dioxide vapor release from the geothermal fluid. A coaxial cable was installed within the same pipeline trench, from the heat exchanger to the well for instrumentation and controls. The pipeline installation was completed the first week of April, 1983.

The pipeline route is located along the western edge of Arrowhead Avenue. The route is located within the right-of-way but off of the paved area to avoid the cost of repaving the street and to reduce conflict with the number of underground utilities in the area. A utility easement was obtained for the area between Orange Show Road and the Wastewater Treatment Plant property to provide the most direct route for the transmission pipeline. Figure 7 displays the pipeline route.

MEEKS & DALEY
WELL #66



CENTRAL AVE.

BENEDICT ST.

HILL CREST AVE.

SCALE 1" = 400'

SO. E. ST.

ORANGE SHOW ROAD

8" I.D. Preinsulated
and Cased Pressure Pipe

20' Utility Easement



Digester Area of San Bernardino
Wastewater Treatment Plant

INTERSTATE 15

SAN BERNARDINO MUNICIPAL WATER DEPARTMENT

PIPELINE ROUTE FROM MECKS & DALEY #66 WELL
TO DIGESTER AREA OF WASTEWATER TREATMENT
PLANT

DRAWN BY	CHECKED BY	SCALE 1" = 400'	C.O. NO.	
			REF.	SHEET OF
APPROVED BY			DATE	
			1	1

FIGURE 7

4 - SYSTEM DESIGN, TESTING, START-UP

All major construction activities for the project were completed to a level where the system could be tested by April 3, 1983. Official dedication ceremonies were conducted on April 5, 1983 by the Board of Water Commissioners. The system was designed with the capabilities of heating up to three 2 million gallon anaerobic digesters. The phase completed is heating one of the 2 million gallon digesters.

4.1 System Design.

A piping and instrumentation diagram appears as Figure 8 for heating one anaerobic digester with geothermal fluid from Meeks and Daley #66. The symbols used for the diagram are identified in Table 5.


4.1.1 Heat Exchanger.

The preliminary design for heating the anaerobic digester with geothermal fluids at 145°F required a 200 square foot spiral plate heat exchanger. This design transfers 1.5 million Btu's/hr of heat to digester sludge.

When the actual temperature of the resource was known, contact was made with the manufacturer of the existing spiral plate heat exchanger to determine if it could be used. The existing heat exchanger is a Model 160H Spiral Sludge Heat Exchanger manufactured by Alfa-Laval.

Representatives from Alfa-Laval indicated that the existing sludge heat exchanger could utilize the 134°F geothermal fluid to heat the sludge from the digesters. A very important criteria evaluated in utilizing the geothermal fluid in the existing heat exchanger was the quality of the geothermal fluid. An analysis was performed with the results displayed on Table 6. The fluid was of the same or better quality than the treated water used in the boiler system; therefore, it was determined that it would not foul or clog the heat exchanger.

FIGURE 8



SAN BERNARDINO MUNICIPAL WATER DEPARTMENT

PIPING AND INSTRUMENTATION DIAGRAM - GEOTHERMAL HEATING OF ONE ANAEROBIC DIGESTER

DRAWN BY	CHECKED BY	SCALE	C.O. NO.
		NONE	
APPROVED BY	REF.		
	DATE		
	SHEET 1 OF 1		

TABLE 5

KEY TO DRAWING SYMBOLS











	Centrifugal Pump
	Gate Valve
	Check Valve
	Globe Valve
	Well Pump Motor
	Pressure Sustaining Valve
	Locally Mounted Temperature Gauge
	Locally Mounted Pressure Gauge
	Locally Mounted Flow Indicator/Totalizer
ACPP	Asbestos Cement Pressure Pipe
PVC	Schedule 200 PVC Pipe
---	Coaxial Cable
	Instrumentation Control Panel

TABLE 6

ANALYSIS OF WATER SAMPLES FROM THE MEEKS AND DALEY WELL NO. 66

EDWARD S. BABCOCK AND SONS, INC.

TESTED JANUARY, 1983

Sodium	mg/l	116
Calcium	mg/l	9
Magnesium	mg/l	1
Carbonate	mg/l	12
Bicarbonate	mg/l	88
Boron	mg/l	2.2
Iron	mg/l	.02
Chloride	mg/l	82
Sulfate	mg/l	32
Nitrate	mg/l	48
Total Dissolved Residue	mg/l	290
Total Hardness as:		
Ca CO ₃	mg/l	27
pH		8.6
Fluoride	mg/l	4.4

The existing heat exchanger is a 150 square feet "sludge type" spiral heat exchanger fabricated of 1/4 inch carbon steel. The original design criteria are listed below:

	<u>SLUDGE</u>	<u>WATER</u>
Capacity Btu/Hr		1,530,000
Flow GPM	306	306
Inlet Temperature °F	90	155
Outlet Temperature °F	100	145
Pressure drop in feet of water	10	6

Water Department staff conducted flow tests utilizing the geothermal fluid to determine if the existing heat exchanger would work. The average requirement for the east digester during the test period was 700,000 Btu's per hour. The maximum heat requirement is 1.5 million Btu's per hour. Testing was conducted under two conditions. The first test was conducted when the well was flowing artesian with a maximum flow rate of 165 gpm. Results of the test are displayed on Table 7. A second test was conducted after a pump was installed on Meeks and Daley #66 well. Results of the test are displayed on Table 8. Test results indicate the existing heat exchanger is sufficient to transfer the required heat from the geothermal fluid to the sludge.

4.1.2 Pump and Motor - Meeks and Daley #66.

Meeks and Daley #66, acquired in January, 1983, has been and continues to flow artesian. The rate of flow has been as high as 3,000 gpm during the winter months when most other wells in the artesian pressure zone are not operating. During April, 1983, the well developed a static pressure of 20 psi. With this condition, sufficient flow and pressure existed to utilize the geothermal energy without pumping. Other wells in the vicinity were turned on as the demand for water increased, and the artesian flow decreased to less than 1,000 gpm with 4 to 5 psi residual pressure. This condition does not permit gravity flow use of the geothermal energy at the Wastewater Treatment Plant.

FLOW TEST ON EAST DIGESTER
HEAT EXCHANGE
MEEKS AND DALEY #66 WELL FLOWING ARTESIAN

TABLE 7

TEST NUMBER	GEOTHERMAL FLUID DATA							SLUDGE DATA						
	BTU/HOUR TRANSFER TO SLUDGE	BTU/HOUR REMOVAL FROM GEOTHERMAL	DELTA $t^{\circ}F$	GEOTHERMAL TEMP (OUT) $^{\circ}F$	GEOTHERMAL TEMP (IN) $^{\circ}F$	GEOTHERMAL FLOW GPM	SLUDGE PUMPED GPM	DELTA t	SLUDGE TEMP (OUT) $^{\circ}F$	SLUDGE TEMP (IN) $^{\circ}F$	SLUDGE PUMP TOTAL HEAD	SLUDGE PUMP DISCHARGE HEAD	SLUDGE PUMP SUCTION HEAD	SLUDGE PUMP RPM
1.	490,392	680,544	17 $^{\circ}$	114 $^{\circ}$	131 $^{\circ}$	80	490	2 $^{\circ}$	94 $^{\circ}$	92 $^{\circ}$	16.17	34.65	18.48	740
2.	750,600	720,576	16 $^{\circ}$	114 $^{\circ}$	130 $^{\circ}$	90	250	6 $^{\circ}$	96 $^{\circ}$	90 $^{\circ}$	24.90	42.70	17.78	840
3.	875,700	910,728	14 $^{\circ}$	116 $^{\circ}$	130 $^{\circ}$	130	250	7 $^{\circ}$	97 $^{\circ}$	90 $^{\circ}$	24.90	42.70	17.78	840
4.	810,648	845,676	13 $^{\circ}$	117 $^{\circ}$	130 $^{\circ}$	130	270	6 $^{\circ}$	96 $^{\circ}$	90 $^{\circ}$	27.70	43.90	16.17	900
5.	788,130	908,226	11 $^{\circ}$	121 $^{\circ}$	132 $^{\circ}$	165	525	3 $^{\circ}$	95 $^{\circ}$	92 $^{\circ}$	15.48	34.65	19.17	740
6.	760,608	990,792	12 $^{\circ}$	120 $^{\circ}$	132 $^{\circ}$	165	380	4 $^{\circ}$	96 $^{\circ}$	92 $^{\circ}$	22.46	40.65	17.78	840

TABLE 8

FLOW TEST ON EAST DIGESTER
HEAT EXCHANGE
MEEKS AND DALEY #66 WELL PUMPED
August 11, 1983 - Mike Lowe

GEOTHERMAL FLUID DATA	BTU/HOUR TRANSFER TO SLUDGE X 1 MILLION	1.2	1.4	1.6
	BTU/HOUR REMOVAL FROM GEOTHERMAL X 1 MILLION	1.2	1.4	1.6
	DELTA $t^{\circ}F$	8 $^{\circ}$	8 $^{\circ}$	8 $^{\circ}$
	GEOTHERMAL TEMP (OUT) $^{\circ}F$	128 $^{\circ}$	128 $^{\circ}$	128 $^{\circ}$
	GEOTHERMAL TEMP (IN) $^{\circ}F$	136 $^{\circ}$	136 $^{\circ}$	136 $^{\circ}$
	GEOTHERMAL FLOW GPM	300	350	400
	SLUDGE PUMPED GPM	300	350	350
SLUDGE DATA	DELTA t°	8 $^{\circ}$	8 $^{\circ}$	9 $^{\circ}$
	SLUDGE TEMP (OUT) $^{\circ}F$	108 $^{\circ}$	108 $^{\circ}$	109 $^{\circ}$
	SLUDGE TEMP (IN) $^{\circ}F$	100 $^{\circ}$	100 $^{\circ}$	100 $^{\circ}$
	SLUDGE PUMP TOTAL HEAD	12.71	12.71	12.71
	SLUDGE PUMP DISCHARGE HEAD	32.34	32.34	32.34
	SLUDGE PUMP SUCTION HEAD	19.63	19.63	19.63
	SLUDGE PUMP RPM	650	650	650
TEST NUMBER		1	2	3

Specifications were developed to furnish and install pumping equipment for the well. A 500 gpm pump was specified with a depth setting of 100 feet. The specifications required an overall pump efficiency of 70% with a total dynamic head (TDH) of 120 feet. Informal bids were received and a contract awarded for installation of a Peabody Floway vertical turbine pump with a vertical hollow shaft 25 hp motor. The column assembly is 100 feet with a three stage 10 DOL Peabody Floway bowl assembly.

4.1.3 Disposal of Geothermal Fluid.

The method for disposal of the geothermal fluids after use was a determination that had to be made after the quality of the resource was known. Water chemical quality samples taken from Meeks and Daley #66 Well, displayed on Table 6, were submitted to John Carollo Engineers to determine if the geothermal fluid could be safely added to the plant tertiary treated effluent without violating established discharge standards. The analysis concluded that a 5 : 1 dilution of geothermal water with treated effluent would make the geothermal water suitable for irrigation. The major chemical constituents in the geothermal water that prevent direct irrigation use are sodium, chloride and boron. Blending the geothermal water with the treated tertiary effluent reduce the constituents to within acceptable levels.

Based on the results of the analysis, the method of discharge selected was to install a six inch pipeline from the heat exchanger to the tertiary reservoir and utilize the stripped geothermal water for in-plant use. The Wastewater Treatment Plant utilizes tertiary water for irrigation, washdown water, and engine cooling water.

5 - PROJECT COST SUMMARY AND CONCLUSION

Total project costs incurred are \$508,600. The costs include re-source confirmation and development, purchase and installation of transmission and distribution facilities, retrofit of heat exchangers to utilize geothermal energy, and system testing. The State of California's portion of the costs is \$390,600, representing 76.8% of the total project costs. Table 9 presents a summary of project costs.

5.1 Projected Natural Gas Savings.

The objective of this project was to utilize low-temperature geothermal energy to provide heat for primary anaerobic digesters at the San Bernardino Wastewater Treatment Plant. Peak heating demand for one digester is 1.5 million Btu's per hour. The annual average heat requirement is 500,000 Btu's per hour. The average annual heat hour requirement is used to determine the offset of natural gas usage.

Based upon heating requirement for one full year, the natural gas offset is determined as follows for one digester:

$$\begin{aligned} & 500,000 \text{ Btu/Hr} \div 100,000 \text{ Btu's per therm} \times 8760 \text{ hours per year} \\ & \div 80\% \text{ efficiency of boiler} = 54,750 \text{ therms of natural gas/year.} \end{aligned}$$

By 1986, two digesters will be heated with geothermal energy and the natural gas offset will be 109,500 therms per year. Capability will be available to heat by geothermal energy three of four digesters resulting in savings of 164,250 therms of natural gas per year.

5.2 Cost Comparison of Geothermal Energy to Natural Gas.

The direct cost of geothermal energy is substantially lower than the cost of natural gas. The cost of maintenance and repair has not been included for

TABLE 9

SUMMARY OF PROJECT COSTS
FOR DIRECT USE OF GEOTHERMAL ENERGY
AT THE SAN BERNARDINO WASTEWATER TREATMENT PLANT

1. Resource Confirmation and Development:		
(a) Resource Confirmation:		
Development of drilling program, drilling and logging of four (4) thermal gradient wells.		\$266,337.00
(b) Resource Development:		
Acquisition of Meeks and Daley #66 Well and reequipping of well.		62,654.00
		\$328,991.00
2. Purchase and installation of transmission facilities, retrofit of heat exchanger		
		176,724.00
3. Testing of system and reports to the California Energy Commission		
		2,885.00
TOTAL PROJECT COSTS.....		\$508,600.00

either the geothermal facilities or the natural gas boiler system. If such a comparison were to be made, however, the geothermal system would be a less expensive system to maintain.

Cost per therm of usable geothermal energy is based upon the following:

- Power costs to deliver one (1) acre foot of water: $1.023 \times 105 \text{ feet TDH} \times \$0.07 \text{ per KWH} \div 70\% \text{ efficiency of pump} = \10.74 per acre foot. This is a conservative calculation which assures 100 percent use of the well pump. In fact, the natural artesian head is adequate for one digester for four months out of the year.
- Therms per acre foot of geothermal water: $43,560 \text{ ft.}^3 \text{ (acre foot of water)} \times 62.4 \text{ pounds per ft.}^3 \times 14^\circ\text{F } (\Delta t) \div 100,000 \text{ Btu's per therm} = 380.53 \text{ therms per acre foot.}$ This Δt is based upon average use. In fact, the usable heat, as shown on Table 7, can be as high as 17°F .
- Power cost per therm: $\$10.74 \div 380.53 \text{ therms per acre foot} = \$0.0282 \text{ per therm.}$
- Amortization of facilities based upon 43,800 therms per year: $\$20 \text{ per therm.}$ Amortized cost per therm is strictly straight-line depreciation costs over the useful life of the facilities to include wells, well pumps, pipelines, and appurtenant facilities. The useful life of the components are: pumping equipment - 10 years; pipeline - 35 years; well - 20 years.
- Total cost per therm: $\$0.0282 \text{ (power cost)} + \$0.20 \text{ (amortization cost)} = \$0.2282.$

The current cost of natural gas from the Southern California Gas Company is $\$0.72$ per therm, or 315% higher than the cost per usable therm of geothermal

energy. If electrical and natural gas costs escalate at the same rate, the cost of geothermal energy becomes even more cost effective, since the power required to produce the geothermal heat represents a small portion of the total cost. From other studies, however, it is likely that natural gas prices will escalate faster than electrical prices.

The total therms required to heat the digester with geothermal energy are less than the therms of natural gas due to the operating losses of the boiler at 80% efficiency. Based upon an average annual hourly requirement of 500,000 Btu's per hour per digester, it will require 54,750 therms of natural gas to provide the equivalent heat of 43,800 therms of geothermal direct use energy.

The use of geothermal energy to provide the annual heat requirements for one digester offsets the cost of \$39,420 of natural gas based upon today's cost, and results in a cost savings of \$29,425. By 1986, additional geothermal energy will be used to heat at least one additional anaerobic digester, and the cost savings will increase to \$58,850 at 1983 prices. If natural gas costs rise as projected, the savings will increase significantly.

With two digesters being heated by geothermal energy, the simple pay back is 8.6 years for the total project costs. The pay back period will be reduced as natural gas prices continue to increase.

5.3 Conclusions.

The utilization of low temperature geothermal energy at the San Bernardino Wastewater Treatment Plant provides a working model to demonstrate the efficiency and effectiveness of the use of this renewable energy resource.

The resource confirmation segment of this project provides sufficient data showing a large geothermal resource that, with proper management, can be utilized for a long period of time.

The results obtained from the project provide impetus for more and varied uses of low temperature geothermal energy with the San Bernardino area. The knowledge gained through this project will be invaluable in the next step, the creation of a geothermal district heating system, which will get underway in September, 1983.

APPENDIX A

Stratigraphic and Geologic Data - Temperature Gradient Wells

Plate II
Plate III
Plate IV
Plate V
Plate VI
Plate VII




PLATE II

REPUBLIC GEOTHERMAL, INC.

11520 E. ELAMORE AVE., SANTA FE SPRING, CA. 92706 (714) 846-2843

TEMPERATURE GRADIENT/ OBSERVATION WELL TQ #1

DRAWN BY: RUI STAFF

DATE: MAY 1982

CHECKED: C.F.L.

SCALE: AS NOTED

APPROVED:

DWG NO.

RGI CS30





PLATE III


REPUBLIC GEOTHERMAL, INC. 11225 S. BLANCKSON AVE., SANTA FE SPRING, CA 92687 913/945-2817			
TEMPERATURE GRADIENT/ OBSERVATION WELL TG#2			
DRAWN BY: RGI STAFF	DATE: MAY 92		
CHECKED: C.F.I.	SCALE: AS NOTED		
APPROVED:	DWT NO.	RGI C011	

PLATE IV

REPUBLIC GEOTHERMAL, INC.
 1122 E. BLAIRMONT AVE., SANTA FE SPRINGS, CA 90703 (714) 946-3441

TEMPERATURE GRADIENT / OBSERVATION WELL TQ #4A

DRAWN BY: RGI STAFF CHECKED: C.F.I. APPROVED:	DATE: MAY 1982 SCALE: AS NOTED DWD NO. RGI C379
---	---







PLATE VI

REPUBLIC GEOTHERMAL, INC.

11223 S. BLANCKSON AVE., SANTA FE SPRING, CA 92705 (714) 948-2401

GEOLOGIC CROSS SECTION A-A'

DESIGNED BY: RGI Staff	DATE: MAY 1982
CHECKED: C.F.I.	SCALE: AS NOTED
APPROVED:	DWG NO. HJL C828



APPENDIX B

Data Concerning TG No. 1

GWH

REPUBLIC GEOTHERMAL INC.

11623 EAST SLAUSON AVENUE SUITE ONE
SANTA FE SPRINGS, CALIFORNIA 90670

TWX. 910.526.1696

(213) 945.3661

April 30, 1982

Mr. Joseph F. Stejskal
San Bernardino Municipal Water Department
P.O. Box 710
San Bernardino, California 92403


Dear Joe:

Enclosed is a lithologic summary of Well TG-1 with Republic's preliminary geologic interpretations therefrom.

This hole and all of the others will be reevaluated after equilibrated thermal gradient data have been acquired and assessed.

Please call if you have any questions.

Sincerely,



G. W. Hutterer
Project Manager

GWH:sjo
Enclosure

cc: E. W. Wellbaum
D. A. Campbell
C. F. Isselhardt
P. P. Parmentier
R. E. Yarter

REPUBLIC GEOTHERMAL, INC.

MEMORANDUM

TO: G. W. Buttrer April 27, 1982
FROM: P. P. Parmentier *ppp*
SUBJECT: Lithologic Summary of Well TG-1 with Preliminary
Geologic Interpretation

Lithology

The lithology of the formations encountered in the San Bernardino Municipal Water District (SBMWD) well TG-1 was determined by examination of the drill cuttings collected at 10-foot intervals.

In well TG-2, electric logs were used to further define the interpreted lithology; however, in TG-1 no self-potential or resistivity log could be obtained in the open hole because of the sloughing of the rock formations. A gamma ray log and a preliminary temperature survey were eventually run in the cased hole, and the results of these surveys are described below.

The formations encountered in TG-1 were basically similar to the rocks encountered in TG-2, consisting of alternating layers of silty clay, medium to very coarse sands, and medium to coarse gravel beds. The detailed description of the lithologic units (Appendix A) and the lithologic column (Figure 1) show that sediments in the upper 610 feet are intercalated gray to pink, medium to coarse sands (mostly granitic and lithic fragments), gravel beds (usually 10 to 20 feet thick), and silty clays 10 to 20 feet thick.

The formations encountered below 610 feet consist of dark gray, medium to coarse sands (locally fairly rich in clay), and one thick, silty clay layer. The different sand layers below 610 feet display remarkable homogenous lithology and grain size. Discrete horizons are up to 50 feet thick, with one clay zone (730 to 790 feet) that appears to be about 60 feet thick.

Memorandum to G. W. Hutterer
April 27, 1982
Page 2

Preliminary Interpretation and Comparison with the Lithology of TG-2

As in TG-2, all the formations encountered in TG-1 appear to be of sedimentary origin. The formations above a depth of 610 feet in TG-1 are interpreted to be Quaternary alluvium deposits. The formations below this depth are tentatively assigned to the Tertiary San Timoteo Formation, similar to those found in TG-2 below 720 feet. The Quaternary formations in TG-1 appear to contain fewer clay layers and to be somewhat thinner than in TG-2. This characteristic could be significant in the control of ground-water circulation. The formation below 610 feet in TG-1 greatly resembles that encountered below 720 feet in TG-2. The 110-foot discrepancy of the elevation of the Quaternary/Tertiary boundary between the two wells will have to be considered when developing an interpretation of the structural role of the Loma Linda fault. At this stage, however, additional data are needed to ascertain the geometric, three-dimension configuration of the Loma Linda fault. It is anticipated that these data will be acquired by drilling the next two thermal gradient wells.

Gamma Ray Logging of TG-1

A gamma ray log was run to a depth of 737 feet in the cased portion of TG-1 on April 13, 1982. The amplitude of the recorded signals was fairly low, probably due to the thick cement zone which impeded the reception of the gamma ray signals. The observed variations in the gamma ray signature were confirmed by several repetitive runs, and the log will be tentatively interpreted after a similar gamma ray log is run in TG-2, in which good self-potential, resistivity, lithologic, and temperature logs are available.

Preliminary Temperature Survey

A preliminary temperature survey was run to a depth of approximately 725 feet. Although the measured temperatures most certainly do not represent equilibrated values, this preliminary survey shows that the temperature seems to increase in the Tertiary rock formations, and this suggests that the Tertiary/Quaternary stratigraphic boundary does not play a hydrologic role as important in TG-1 as observed in TG-2.

The final measurement of the temperature in TG-1 will show equilibrated temperature values. The data will contribute to interpretation of the geometric configuration of the Loma Linda fault and of its hydrologic significance.


PPP:sjo
Attachment

Appendix A

- 0-20 feet: Pink, medium sand, well-sorted, with subrounded fragments of mostly granitic origin.
- 20-30 feet: Pink, coarse gravel.
- 30-40 feet: Gray, silty clay.
- 40-60 feet: Pink, medium sand, moderately sorted, with 5% gravel-size grains and 5% mafic grains.
- 60-80 feet: Very coarse gravel with subrounded lithic rock fragments.
- 80-100 feet: Gray, silty clay.
- 100-150 feet: Gray, medium sand, with 20% mafic subangular grains, well-sorted, and locally 5% gravel-size grains.
- 150-160 feet: Coarse sand, similar in lithologic composition to that logged between 100-150 feet.
- 160-170 feet: Gray, coarse gravel with subrounded lithic fragments.
- 170-180 feet: Gray, silty clay.
- 180-190 feet: Sample missing.
- 190-240 feet: Grayish-pink, medium sand, well-sorted, locally with subangular, gravel-size, lithic fragments, and traces of clay.
- 240-270 feet: Clayey, medium to coarse sand, well-sorted.
- 270-300 feet: Pink, gravelly medium sand, well-sorted.
- 300-310 feet: Sample missing.
- 310-330 feet: Pink, gravelly medium sand, well-sorted.
- 330-350 feet: Medium to coarse gravel, poorly sorted, with mostly granitic lithic fragments.
- 350-360 feet: Pink, medium sand, well-sorted.
- 360-370 feet: Sandy, coarse gravel, similar to 330-350 feet.
- 370-380 feet: Gravelly, medium sand.
- 380-390 feet: Clayey, medium sand.

- 390-460 feet: Pink, medium sand, poorly sorted, locally with up to 10% gravel-size lithic fragments.
- 460-480 feet: Clayey, coarse sand, poorly sorted, with gravel-size angular lithic fragments.
- 480-490 feet: Well-sorted medium sand.
- 490-500 feet: Clayey, medium to coarse sand.
- 500-530 feet: Pink, medium sand, moderately sorted, with 5% mafic grains.
- 530-540 feet: Medium gravel with subangular lithic fragments.
- 540-550 feet: Well-sorted medium sand.
- 550-580 feet: Clayey, pink, medium sand, moderately sorted.
- 580-610 feet: Gray, silty clay.
- 610-660 feet: Dark gray, coarse sand, slightly clayey, moderately sorted with subangular grains, dominantly mafic grains.
- 660-690 feet: Same coarse sand as 610-660 feet, with more clay and dominant mafic grains.
- 690-730 feet: Dark gray, clayey, medium sand, well-sorted, with predominantly mafic grains.
- 730-770 feet: Dark gray, silty clay.
- 770-790 feet: Brown, silty clay.
- 790-820 feet: Dark gray, medium sand, well-sorted, with subangular lithic fragments of granitic and schistose composition.

FIGURE 1
 SAN BERNARDINO MUNICIPAL WATER DISTRICT
 TEMPERATURE GRADIENT/OBSERVATION WELL TG # 1
 LITHOLOGIC COLUMN



APPENDIX C

Data Concerning TG No. 2

GWH

REPUBLIC GEOTHERMAL, INC.

11823 EAST SLAUSON AVENUE
SANTA FE SPRINGS, CALIFORNIA 90670

TWX - 910-386-1696

(213) 943-3661


April 5, 1982

Mr. Joseph Stejskal
City of San Bernardino Water Department
300 North D Street
San Bernardino, California 92401

Dear Joe:

Attached, for your information, is a memorandum related to our preliminary interpretation of data from TG-2. Please call if you have any questions.

Sincerely,


G. W. Eubler
Project Manager

GWE:sjo
Attachments

REPUBLIC GEOTHERMAL, INC.

MEMORANDUM

TO: G. W. Hutterer April 5, 1982

FROM: P. P. Parmentier *Paul P. Parmentier*

SUBJECT: Lithologic Summary of Well TG-2 with Preliminary
Geologic Interpretation

Lithology

The lithology of the formations encountered in the San Bernardino Municipal Water District (SBMWD) well TG-2 were determined by examination of the drill cuttings collected at 10-foot intervals. The lithologic sequence is further defined by the open-hole electric logs which will be described later.

The formations encountered in TG-2 consist principally of successive alternating layers of silty clay, medium to very coarse sand, and medium to coarse gravel beds. The detailed description of the lithologic units (Appendix A) and the lithologic column (Figure 1) show that sediments in the upper 700 feet consist of alternating silty clay zones, locally fairly thick at depths of 340-430 feet, 600-620 feet, and 680-700 feet; medium to coarse sand zones with grains of diverse lithologic origin and gravels, locally fairly thick at depths of 120-240 feet, 430 to 460 feet, and 660 to 680 feet. The formations encountered below 700 feet consist of intercalated very coarse sands and clay layers. The different sand layers display remarkably homogeneous lithology and grain size, with thicknesses up to 90 feet, and the clay zones appear to be up to 60 feet thick.

Preliminary Interpretation

All of the formations encountered in TG-2 appear to be of sedimentary origin. The formations above 720 feet are interpreted to be Quaternary alluvium deposits. The formations below this depth are tentatively assigned to the San Timoteo formation of Tertiary to Quaternary age, the nearest outcrops of which are approximately three miles south of TG-2.

Memorandum to G. W. Hutterer
April 5, 1982
Page 2

The San Timoteo rocks seen in the outcrop comprise layers of mostly unconsolidated sand and gravel, a few inches to several feet thick, with local silt and clay interbeds. In outcrops located near the San Jacinto fault, these formations dip steeply in tight folds and fault blocks. The homogeneity of the lithology observed from about 700 feet to total depth in TG-2 suggests that the formations may have been penetrated diagonally, showing apparent bed thicknesses that are much greater than actual thickness values. It is possible that sharp bending of these rocks near the Loma Linda fault zone may be partially responsible for the "aquatard" effect of the fault zone.

The unconformable contact between the upper, more recent sediments and the lower San Timoteo formation has tentatively been set at about 720 feet. The effect of this boundary on the local hydrothermal circulation may later be observed in the temperature profile of the well.

Electric Logging of TG-2

Two simultaneous electric logs (Self Potential and Resistivity) were run in TG-2 on March 30, 1982, before cementing of the 2-3/8" tubing. Due to time constraints, no gamma ray log was run, but the SP and resistivity log will provide sufficient information for correlation with other wells and for future perforation of this well.

Although the SP log does not have strong character and appears locally to be "reversed," it reflects adequately the results of the resistivity log, which defines fairly precisely the alternating clay, sand, and gravel layers. The lithology that can be interpreted from the electrical log corresponds fairly well with the lithology described from the cuttings, and it additionally defines some minor lithologic units within the broader lithologic layers described from the geology.

The SP variations observed below a depth of about 730 feet appear to be less distinct than the those observed at shallower depths. This could be due to the fact that the San Timoteo formation lithologic boundaries may be dipping at fairly high angles, thereby minimizing changes in the signature of the SP curve in that unit. Our belief that a stratigraphic boundary exists at approximately 700 feet is supported by this change in character in the electric logs.

PPP:sjo
Attachment


APPENDIX A

0-50	feet	Medium-grained sand with angular grains of quartz, feldspars, and lithic fragments.
50-120	feet	Coarse sand with varying proportion of medium-grained sand with similar grain composition as 0-50 foot depth interval.
120-240	feet	Gravel with varying proportion of coarse sand, with angular to subangular grains of feldspars, quartz, and mafic lithic fragments.
240-270	feet	Very coarse sand with both lithic fragments and mineral grains.
270-280	feet	Medium-grained sand with minor amounts of clay.
280-340	feet	Coarse sand with various amounts of clay and gravel-size grains of granitic mineral composition and lithic fragments.
340-430	feet	Gray, silty clay of fairly constant lithology.
430-460	feet	Gravel, with minor amounts of sand and clay.
460-510	feet	Very coarse sand with minor clay, similar to 280-340 feet.
510-520	feet	Gray, silty clay
520-540	feet	Medium-grained sand, similar to interval 280-340 feet.
540-550	feet	Brown, silty clay
550-600	feet	Very coarse sand with varying amounts of gravel and clay.
600-620	feet	Brown, silty clay.
620-660	feet	Medium-grained sand with approximately 70% mafic grains.
660-680	feet	Coarse gravel consisting of lithic fragments.

680-700	feet	Brown, silty clay.
700-710	feet	Medium-grained sand, similar to interval 620-660 feet.
710-720	feet	Brown, silty clay.
720-760	feet	Medium-grained sand with various amounts of clay and minor amounts of white chalk grains.
760-780	feet	Dark gray, silty clay.
780-850	feet	Very coarse sand with 5% gravel.
850-860	feet	Brown, silty clay.
860-870	feet	Very coarse sand, similar to interval 720-760 feet.
870-880	feet	Brown, silty clay.
880-900	feet	Very coarse sand, similar to interval 720-760 feet.
900-960	feet	Brownish gray, silty clay.
960-1030	feet	Very coarse sand with large proportion (25%) of pink K-feldspar grains.
1030-1060	feet	Very coarse sand with numerous mafic grains and minor amounts of biotite.
1060-1100	feet	Gray, silty clay.
1100-1110	feet	Very coarse sand, similar to interval 1030-1060 feet.
1110-1160	feet	Brown to dark gray, silty clay.
1160-1250	feet	Very coarse sand with subangular grains having 10% pink grains, 20% white grains, 20% greenish gray grains, 20% gray grains, and 10% black, mafic grains.
1250-1280	feet	Dark gray, silty clay.
1280-1370	feet	Very coarse sand, same as 1160-1250 feet.

FIGURE 1

**SAN BERNARDINO
MUNICIPAL WATER DISTRICT
TEMPERATURE GRADIENT/OBSERVATION WELL TG #2**



APPENDIX D

Data Concerning TG No. 4A

GWH

REPUBLIC GEOTHERMAL, INC.

11823 EAST SLAUSON AVENUE
SANTA FE SPRINGS, CALIFORNIA 90670

TWX . 910.586.1696

(213) 945.3661

May 21, 1982


Mr. Joseph P. Stejskal
San Bernardino Municipal Water Department
P.O. Box 710
San Bernardino, California 92403

Dear Joe:

Enclosed is our summary report concerning TG-4A. I think that the document is self-explanatory, but don't hesitate to call if you have questions.

We are currently writing a report that discusses all of the thermal gradient wells, their geology, their thermal aspects, and the overall scenario. We will, in this report, be recommending, prioritizing, and justifying one or more alternative sites for the production well.

Sincerely,


G. W. Hutter
Project Manager

GWE:sjo
Enclosure

cc: E. W. Wellbaum
J. R. Stites
D. A. Campbell
C. F. Isselhardt
R. E. Yarter

REPUBLIC GEOTHERMAL, INC.

MEMORANDUM

TO: G. W. Hutterer

May 20, 1982

FROM: C.. F. Isselhardt *C.F.I.*

SUBJECT: Lithologic and Temperature Data Summary of Gradient Hole
TG-4A

Lithology

The nature of the sediments penetrated by well TG-4A was determined by visual examination of the drill cuttings collected at 10-foot intervals in a manner similar to that applied to wells TG-2, TG-1, and TG-5A. Both gamma ray and SP-resistivity logs were run in the open hole interval (230-1,500 feet) to enhance lithologic interpretation.

The lithology encountered is basically the same as that found in TG-1, TG-2, and TG-5A and is composed predominantly of intercalated beds of unconsolidated coarse to very coarse-grained sands and pebbly sands, medium-grained gravels, and sandy to silty clays (Figure 1). In this hole, however, the gamma ray and SP logs show that a few sands are up to 45 feet thick. The lithology, as interpreted from cuttings, does not always agree well with interpretations made from electric logs, especially in the bottom 150 feet of the hole where the cuttings' samples (Appendix A - Sample Descriptions) are all clay and where the logs indicate sand predominating. The probable explanation for this discrepancy is that the cuttings' samples were not taken at the proper time.

The contact between the Quaternary alluvium and the Tertiary San Timoteo Formation is placed at 620 feet based on the marked increase in dark lithic fragments of schist and gneiss in the sands and gravels at that point. The E-logs, however, show no noticeable change in this area. As in the other wells, the sands of the San Timoteo Formation appear to be better sorted than those in the Quaternary alluvium. On the electric logs, particularly the SP, there appears to be more sand between 740 feet and 1,500 feet than in the interval from the ground surface to 740 feet.

Preliminary Interpretation and Comparison with Other Wells

Well TG-4A is the deepest hole drilled to date (1,500 feet). As in the other three holes, the units penetrated are unconsolidated Quaternary alluvial sediments and clays, sands, and gravels assigned to the Tertiary San Timoteo Formation. Although TG-4A is only about 200 feet from TG-1, the lithologic sequences differ somewhat, reflecting the Santa Ana River channel-type (complexly braided) sedimentary environment.

The structural and temperature data gleaned from this well have added to our knowledge considerably, but they are puzzling in some respects. Of especial interest is the fact that while the top of the San Timoteo Formation dips generally to the west, the maximum temperature isotherms dip to the south-southeast. This may reflect the effect of structural control on the hydrothermal system that apparently cuts across stratigraphic boundaries.

Logging of TG-4A

Well TG-4A was logged with a different instrument than that used in the other wells, and we were, therefore, able to get high quality gamma ray and SP-resistivity logs. These logs provided excellent sand-shale discrimination and show some interesting apparent SP reversals in several portions of the well (particularly the last 200+ feet). These reversals may, if they are real, be due to changes in water salinity that, in turn, may be related to temperature changes in the ground water.

Preliminary Temperature Survey

A preliminary temperature survey was run to a depth of 1,300 feet on May 13, 1982, about six days after completion of the well (Figure 2). The temperature probe was unable to go below 1,300 feet (tubing was run to 1,495 feet), probably due to residual cement in the tubing.

This temperature profile, though not completely equilibrated, indicates very clearly the convective and maximum temperature zone that extends from about 780 to 875 feet. The top of this zone coincides closely with the top of the aquifer in well TG-5A (775 feet), although it is not as thick and has a higher temperature (49°C versus 45°C). A final temperature survey will be conducted on May 19, 1982, but neither the temperature gradient profile nor the absolute temperatures are expected to change significantly.


Memorandum to G. W. Hutterer
May 20, 1982
Page 3

The temperatures encountered indicate that this aquifer contains a mixture of thermal (+56°C) and nonthermal waters similar to those interpreted to exist in TC-5A.

CFI:sjo

Attachments

FIGURE 1
TG 4A STRATIGRAPHIC COLUMN



APPENDIX A

WELL TG-4A SAMPLE DESCRIPTIONS

0-10	feet	Sand-pink-white-light gray, coarse to very coarse, angular, unconsolidated, well-sorted, arkosic, with pink K-feldspars and some dark gray rock fragments.
10-70	feet	Sand-as above, predominantly very coarse-grained.
70-80	feet	Sand-as above, with 15% gravel, predominantly dark gray rock fragments.
80-100	feet	Sand-as above, with 5-10% gravel.
100-130	feet	Sand-as above, coarse-grained, well-sorted, only trace gravel.
130-150	feet	Clay-medium gray, soft, with 5% sand.
150-160	feet	Sand-multicolored, as above, with 5% gray clay, rare gravel.
160-170	feet	Gravel-multicolored, as above, angular-subangular, with 10% gray clay.
170-210	feet	Sand-as above, medium- to coarse-grained, with 20% gravel, no clay.
210-220	feet	Sand-as above, coarse to very coarse, with 15-20% gravel.
220-230	feet	Sample missing.
230-240	feet	Sand-as above, medium- to coarse-grained, with 15-20% gravel.
240-250	feet	Sand-as above, with 30% gravel.
250-280	feet	Gravel-well sorted, 1/2" diameter, trace sand.
280-350	feet	Sand-unconsolidated, multicolored, medium- to coarse-grained, with 15-20% 1/4" gravel.
350-410	feet	Sand-as above, becoming coarse to very coarse, with 30-40% gravel.
410-430	feet	Sand-as above, coarse-grained, well-sorted, angular, with 5% gray clay.
430-440	feet	Clay-brownish gray, soft, with 20% coarse sand, as above.

440-460	feet	Gravel-multicolored, angular, unconsolidated, with 20% coarse sand.
460-470	feet	Clay-light brown, soft, with 10% coarse sand and gravel.
470-480	feet	Sand-very coarse, with 10-15% gravel and 20% clay, as above.
480-490	feet	Sand-as above, with 5% clay.
490-500	feet	Sand-medium- to coarse-grained, multicolored, with 5% gravel.
500-550	feet	Clay-light brown, soft, with trace -5% sand
550-560	feet	Sand-coarse to very coarse-grained, well-sorted, multicolored, with pink K-feldspars, as above, with trace gravel.
560-620	feet	Clay-light brown, soft, with trace -few % sand.
620-660	feet	Sand-unconsolidated, multicolored but darker gray overall, marked increase in dark gray rock fragments (San Timoteo Formation), medium-coarse grained, with trace gravel.
660-680	feet	Sand-as above, with slight increase in pink feldspar fragments and trace - 5% clay.
680-710	feet	Clay-medium gray, soft, with 5% sand.
710-760	feet	Clayey sand-multicolored, with abundant dark gray rock fragments, unconsolidated, coarse to very coarse, angular sand with 20-30% gray clay.
760-780	feet	Clay-brownish gray, soft, with <5% sand.
780-830	feet	Sandy clay-gray to brown gray, with 45% sand, coarse to very coarse.
830-840	feet	Sand-unconsolidated, angular, moderately well-sorted, coarse to very coarse sand, as above, with 10% gray clay.
840-850	feet	Sandy clay-brownish gray clay with 30-40% coarse sand.
850-860	feet	Clay-light brown clay with trace sand.
860-870	feet	Sand-coarse to very coarse, unconsolidated, as above, with 5-10% brownish gray clay.
870-880	feet	Sand-as above, no clay.
880-890	feet	No sample.

890-940	feet	Pebbly sand-as above, very coarse, with 10-15% pebbles or fine gravel.
940-980	feet	Sand-multicolored, light to dark gray, angular, coarse to very coarse, well-sorted, as above, with trace - 5% gray clay, no pebbles.
980-1000	feet	Clayey sand-sand, as above, with 15-20% gray clay.
1000-1040	feet	Sand-multicolored, as above, no clay, trace pebbles.
1040-1070	feet	Clay-light brownish gray, soft, with trace sand.
1070-1090	feet	Sand-as above, well-sorted, with 10-15% clay.
1090-1120	feet	Clay-light brownish gray.
1120-1130	feet	Sandy clay-clay as above, with 20% sand, coarse, well-sorted, as above.
1130-1150	feet	Clayey sand-sand as above, with 20-30% clay, as above.
1150-1210	feet	Sandy clay-light brownish gray soft clay, with 5-10% sand, as above, sand increases with depth up to 20% at 1180 feet, then decreases to 5% to 1210 feet.
1210-1240	feet	Sand-light to dark gray, multicolored, (abundant dark gray rock fragments) moderately well-sorted, angular, unconsolidated.
1240-1250	feet	Clay-brownish gray clay, soft, with 5% sand.
1250-1280	feet	Sand-predominantly dark gray rock fragments, as above.
1280-1290	feet	Sandy clay-as above, with 30% sand.
1290-1330	feet	Clayey sand-sand as above, with 20-30% gray clay, as above.
1330-1350	feet	Sandy clay-gray clay, as above, with 20% sand.
1350-1500	feet T.D.	Clay-as above, gray to brownish gray, with 5% sand.

APPENDIX E

Data Concerning TG No. 5A

GUR

REPUBLIC GEOTHERMAL, INC.

11823 EAST SLAUSON AVENUE SUITE ONE
SANTA FE SPRINGS, CALIFORNIA 90670

TWX. 910-586-1696

(213) 945-3661

May 5, 1982


Mr. Joseph F. Stejskal
San Bernardino Municipal Water Department
P.O. Box 710
San Bernardino, California 92403

Dear Joe:

Enclosed is a short, preliminary summary of some physical aspects of well TG-5A. This document has been prepared in the same format as that used to describe wells TG-1 and TG-2. We plan, of course, to integrate data from all the temperature gradient wells prior to recommending a location for the production well.

Please call if you have questions regarding this report or any other matter.

Sincerely,



G. W. Euttrer
Project Manager

GWE:sjo
Enclosure

cc: E. W. Wellbaum
D. A. Campbell
C. F. Isselhardt
P. P. Parmentier
R. E. Yarter

REPUBLIC GEOTHERMAL, INC.

MEMORANDUM

TO: G. W. Euttrer
FROM: C. F. Isselhardt *C.F.I.*
SUBJECT: Lithologic Summary of Gradient Hole TG-5A

May 3, 1982

Lithology

The stratigraphic sequence encountered in the San Bernardino Municipal Water District (SBMWD) well TG-5A was determined by visual examination of the drill cuttings collected at 10-foot intervals.

A gamma ray log was run in this well in the open hole to further define and assist in the lithologic interpretation. The lithologic sequence encountered in this hole is essentially the same as that found in TG-1 and TG-2, composed predominantly of thin (2 to 10 feet) alternating beds of unconsolidated, medium- to very coarse-grained sands and pebbly sands, medium- to coarse-grained gravels, and sandy to silty clays. Although the lithologic descriptions (Appendix A) and the stratigraphic column (Figure 1) indicate some of the sands, gravels, and clays to be relatively thick units, the gamma ray log shows them to be thinner and intercalated. This discrepancy may be attributed to the relatively large sampling interval and the probability that some samples have not been taken at the proper intervals.

As in the other wells drilled to date, the sediments in the Quaternary section (above 600 feet in TG-5A) consist predominantly of unconsolidated sandy gravels, coarse pebbly sands, and silty clays with varying amounts of sand and gravel mixed in. The sands and gravels are generally multicolored (pink-white-gray) and are composed principally of granitic rock fragments and pink potassium feldspar crystals with minor dark lithic fragments. Bed thickness is highly variable, based on sample examination.

Below 600 feet the units are darker gray in appearance, and the percentage of dark lithic fragments of schist and gneiss are much

Memorandum to G. W. Ruttner
May 3, 1982
Page 2

higher. This is interpreted to indicate that the well has penetrated the San Timoteo Formation. The sands appear to be more uniformly sorted, and the clay content generally increases. Several of the units are rich in pink feldspar and granitic rock fragments, making selection of the precise San Timoteo Formation contact difficult. Several discrete sand units in the San Timoteo Formation appear to be 100 feet or more thick in the lower part of the hole, although the gamma ray log indicates the existence of numerous thin shale breaks.

Preliminary Interpretation and Comparison with Other Wells

As with TG-1 and TG-2, all the units penetrated in TG-5A are sedimentary in nature. The lithology above 600 feet is interpreted to be Quaternary alluvial deposits, while the units below this depth are questionably San Timoteo Formation, a Tertiary sedimentary unit of sands, clays, and conglomerates similar to the overlying alluvium.

The contact of the San Timoteo Formation is picked at almost the same depth as in TG-1 and provides another datum point for future structural interpretation.

Logging of TG-5A

TG-5A was successfully logged with the gamma ray tool in the open hole interval 240 feet to 1,400 feet, providing a good quality log with excellent sand/shale discrimination. An SP-resistivity log was also run from 240 feet to 475 feet; unfortunately, the tool failed at that point, and we were unable to conduct any further logging operations.

Preliminary Temperature Survey

On Monday, April 26, 1982, a preliminary temperature survey was run in TG-5A to a depth of 1,335 feet, four days after completion. Although the temperatures measured are not completely equilibrated, the shape of the profile (Figure 2) indicates the zone of convective flow and maximum temperature. It appears that this well did not penetrate the Loma Linda fault which is estimated to be below 2,000 feet at this location.

The zone between 775 feet and 950 feet appears to be an aquifer containing water at 45°C, based on the temperature profile. A final temperature survey will show the equilibrated temperatures but should not change the profile significantly. It is probable

Memorandum to G. W. Huttner
May 3, 1982
Page 3

that the hole is not very far away from the Loma Linda fault (horizontally) and that thermal waters have risen along the fault and entered the 775-950 foot aquifer where they may be mixing with nonthermal ground waters that bring the temperatures down to $\pm 45^{\circ} \text{C}$.

CFI:sjo

Attachments

APPENDIX A

Lithologic Description of Hole TG-5A

0-10 feet	Silty, sandy gravel - tan, with up to 1" diameter pebbles in fine, silty, micaceous sand matrix, unconsolidated.
10-20 feet	Unconsolidated sand - feldspathic, coarse-grained, pink-tan, angular with mica.
20-40 feet	Gravel - unconsolidated, 1/8"-1/4" diameter, white, to dark gray, to pink, angular-subrounded with mafic rock fragments.
40-80 feet	Silty clay - light brown, silty with 10% gravel as above, micaceous.
80-100 feet	Unconsolidated sand - multicolored pink-dark gray, angular-subangular, very coarse sand to fine gravel, 15-20% dark rock fragments.
100-170 feet	Gravelly sand - as above, but getting coarser to medium size gravels.
170-190 feet	Gravelly clay - medium gray clay, with 20-30% sand and gravel as above.
190-200 feet	Unconsolidated gravel - multicolored, angular-subangular, with 10-15% coarse unconsolidated sand.
200-210 feet	Unconsolidated gravel - with 20-25% sand and 5% gray clay.
210-220 feet	Wood fiber material - with some sand and clay, possibly redwood.
220-280 feet	Unconsolidated sandy gravel - as in 190-200 feet with 40% coarse sand.
280-290 feet	Gravel - unconsolidated, poorly sorted, multicolored, subround-angular, 30% pink feldspar.
290-310 feet	Sandy gravel - as above, with 50% coarse to very coarse sand with pink feldspar and granitic rock fragments.
310-330 feet	Clay - tannish gray, with 10-15% sand and gravel.
330-340 feet	Clay - as above, with 40% coarse sand.

340-350 feet	Gravelly sand - multicolored, predominantly granitic, subrounded-angular, unconsolidated, with 20% gray clay, poorly sorted.
350-380 feet	Clay - gray to tan as above, with 30-50% angular coarse sand.
380-400 feet	Gravelly sand - as at 340-350 feet, with 20-25% clay.
400-410 feet	Gravelly sand - as above, with 10-15% tan clay.
410-440 feet	Gravel - with some very coarse sand as above, angular-subangular, with 10% clay.
440-470 feet	Gravel - as above, with no clay, subround-angular.
470-500 feet	Gravel - as above, with 10% very coarse sand and 5% clay.
500-520 feet	Clay - medium brown, plastic, with 5% fine-medium sand.
520-530 feet	Gravel - multicolored, angular-subrounded, unconsolidated.
530-560 feet	Sand - medium-coarse grain, pinkish gray, angular-subangular, well sorted, with 5-10% clay.
560-590 feet	Clay - gray to tannish gray, plastic, with 20-30% medium sand.
590-600 feet	Clay - gray, soft, no sand.
600-620 feet	Gravel - angular-subangular, unconsolidated, predominantly dark gray schistose or gneissic rock fragments.
620-630 feet	Clay - light brown-gray brown, with 40% coarse sand.
630-650 feet	Clay - grayish brown, with 25% sand.
650-680 feet	Clay - medium to dark gray, with only a trace of fine sand.
680-690 feet	Coarse pebbly sand - light to dark gray, unconsolidated, angular-subangular, with 10-15% dark gray clay.
690-700 feet	Coarse sand - as above, with less pebbles and only a trace of clay.

700-730 feet	Clay - brownish gray, soft, with 5-10% medium sand.
730-740 feet	Coarse sand - unconsolidated, pink to dark gray, angular-subangular, with some pebbles and 5% clay.
740-780 feet	Sand - medium-coarse grained as above, no clay.
780-790 feet	Clayey sand - as above, with 40-50% brownish gray clay.
790-810 feet	Clayey sand - as above, with 10-25% clay.
810-820 feet	Sand - medium to coarse grain, unconsolidated, well sorted, with 10% clay.
820-850 feet	Pebbly sand - as above, multicolored, generally lighter colored with abundant pink feldspars, not as well sorted.
850-940 feet	Sand - moderately sorted sand, unconsolidated, with 10-20% clay.
940-960 feet	Clay - light brown, with 10-15% fine-medium sand.
960-1020 feet	Sand - unconsolidated, coarse grained, multicolored, pink-dark gray, pebbly, angular-subangular, with 5-10% clay.
1020-1030 feet	Sand - as above, with 30-40% clay.
1030-1040 feet	Sand - as above, with 10% clay, more pebbly.
1040-1100 feet	Sand - as above, medium-coarse grained, less pebbly, trace to 5% clay.
1100-1300 feet	Sand - fine-medium-coarse, moderately sorted as above, no clay, some pebbles.
1300-1340 feet	Sand - as above, with 5-10% clay.
1340-1400 feet	Sand - as above, with 10-30% clay.
1400-1410 feet	Clay - brownish gray, with 20-30% sand as above.

FIGURE 1

SAN BERNARDINO MUNICIPAL WATER DISTRICT
TEMPERATURE GRADIENT/OBSERVATION WELL-TG # 5A

STRATIGRAPHIC COLUMN

DEPTH (feet)






FIGURE 2
SAN BERNARDINO MUNICIPAL WATER DISTRICT
TEMPERATURE GRADIENT/OBSERVATION WELL-TG # 5A



APPENDIX F

Temperature Profiles


Meeks & Daley #66
TG No. 2



TEST DATE: AUGUST 22, 1983

SAN BERNARDINO MUNICIPAL WATER DEPARTMENT

MECKS & DALEY WELL #66
TEMPERATURE GRADIENT LOG



TEST DATE: AUGUST 23, 1983

SAN BERNARDINO MUNICIPAL WATER DEPARTMENT

TG NO. 2
TEMPERATURE GRADIENT LOG